

**SECTION 015800 – PROJECT IDENTIFICATION AND SIGNS**

**PART 1 – GENERAL**

**1.01 REQUIREMENTS INCLUDED**

- A. Contractor shall provide and be responsible for maintaining and updating the Project identification sign throughout the duration of the Project.
- B. Contractor shall provide temporary on-site informational signs:
  - 1. As may be required by local codes, laws and regulatory agencies.
  - 2. To identify key elements of the construction facilities.
  - 3. To direct traffic.
  - 4. To facilitate trade gate system if required.
  - 5. Provide other signs as may be required such as "NO TRESPASSING", "NO PARKING", Safety Signs, and directional signs as directed by the Construction Manager.
  - 6. To identify public access areas and construction areas so as to maintain an orderly site and protect public safety.
  - 7. As they relate to occupancy and egress requirements for the existing building in conjunction with construction areas.
- C. No other signs shall be displayed.

**1.02 RELATED REQUIREMENTS**

- A. Drawings and general provisions of Contract, including General and Special Conditions.
- B. Section 010100 – SCOPE OF WORK.

**1.03 PROJECT IDENTIFICATION SIGN**

- A. Contractor will anticipate the addition of subsequent panel(s) to the sign after initial construction and installation as contractors are added. Such panels will be added as necessary as requested by the Construction Manager.
- B. Project sign, framing, supports and foundations shall be removed by Contractor when instructed by the Construction Manager or prior to completion and final acceptance, unless instructed by the Construction Manager to be left on the site longer, in which case it will be removed by the Owner.

## **Quil Ceda Creek Counseling Project# QCV-CP-21-003**

---

TULALIP, WASHINGTON

### 1.04 INFORMATIONAL SIGNS

- A. Painted signs with painted lettering or standard products.
  - 1. Size of Signs and Lettering: As required by regulatory agencies or as appropriate to usage.
  - 2. Colors: As required by regulatory agencies, otherwise of uniform colors throughout Project.
- B. Erect at appropriate locations to provide required information or as requested by the Construction Manager.

### 1.05 QUALITY ASSURANCE

- A. Sign Painter: Professional experienced in the type of work required.
- B. Paint Finishes: Adequate to resist weathering and fading for scheduled construction period.

## PART 2 – PRODUCTS

### 2.01 SIGN MATERIALS

- A. Structure and Framing: May be new or used, wood or metal, in sound condition structurally adequate to work and suitable for specified finish.
- B. Sign Surfaces: Exterior softwood plywood with medium density overlay, unless otherwise specified in the Contract Documents, standard large sizes to minimize joints.
  - 1. Thickness: In accordance with details.
- C. Rough Hardware: Galvanized
- D. Paint: Exterior quality.
  - 1. Use Bulletin colors for graphics.
  - 2. Colors for structure, framing, sign surfaces and graphics: In accordance with details.

## PART 3 - EXECUTION

### 3.01 INFORMATIONAL SIGNS

- A. Paint exposed surfaces: One coat of primer and one coat of exterior paint.
- B. Paint graphics in styles, sizes and colors selected.
- C. Install at a height for optimum visibility, on ground-mounted poles or attached to temporary structural surfaces.

**Quil Ceda Creek Counseling Project# QCV-CP-21-003**

---

TULALIP, WASHINGTON

3.02 MAINTENANCE

- A. Maintain signs and supports in a neat, clean condition; repair damages to structure, framing or sign.
- B. Relocate informational signs as required by progress of the Work.

3.03 REMOVAL

- A. Contractor shall remove signs, framing, supports and foundations upon completion of the Project or as requested by the Construction Manager.

**END OF SECTION 015800**